P.O.	Date:	
Contact name:		
Company / Address:		
Phone:	Fax:	

Halo Counter-Sink 1


Double Bowl Worksheet & Order Form

MTI Order Entry Department

Phone: 800-783-8827 Fax: 800-438-8827 Email: orderentry@mtibaths.com

Worksheet

Email:



NOTE: Corner support blocks shown in above 'bottom view' are necessary only when deck height is over 1". All four sides will be finished standard, unless requested otherwise. Important: Due to the handcrafted nature of this product, please allow for a tolerance of up to 1/4" for overall dimensions and 1/2" for bowl placement.

Countertop Measurements - including overhang*

Length	Depth	Deck Heigh
--------	-------	------------

* Add a minimum overhang of 1/4" to length & depth, to ensure full coverage of any exposed side of the vanity. Additional overhang may be required depending on installation application or wall variances.

Bowl Placement Measurements

Length - Enter measurements from Left (L) AND Right (R).

inches (L) from left edge of top to center of bowl.
AND
inches (R) from right edge of top to center of bowl.

Depth - Enter a measurement from Back (B) OR Front (F).

inches (B) from back edge of top to back edge of bowl.
OR

_____inches **(F)** from front edge of top to front edge of bowl.

Installation Type - Choose one	e:
Vanity Mount OR _	Wall Mount
Faucet Application - Choose	one:

_____Deck Mount OR _____ Wall Mount

Order Form - See local MTI dealer for pricing.

Counter-Sink Size - Choose one of the following and enter price:					
Length	Depth	Finish	Part#		Price
40" 19"	Matte	C861-D50MT			
up to 50"	up to 50" up to 24"	Gloss	C861-D50GL		
> 50"	> 50" 19"	Matte	C861-D62MT		
up to 62" up to 24"	Gloss	C861-D62GL			
> 62"	19"	Matte	C861-D74MT		
up to 74" up to	up to 24"	Gloss	C861-D74GL		
> 75	19"	Matte	C861-D86MT		
up to 86"	up to 24"	Gloss	C861-D86GL		

IMPORTANT CONSTRUCTION AND OPTIONS INFORMATION:

- Carefully review inside vanity specifications to ensure that there
 is proper clearance to accommodate the bowl, drain and optional
 integrated overflow, if applicable.
- Please take into consideration the thickness of material under the countertop when positioning sink bowl, using a deck-mounted faucet or adding an integrated overflow. See "bottom view" drawing above.
- Outside of overflow housing protrudes approx. 1/2" from the bowl and may impact bowl placement.
- Please submit a copy of vanity specifications with order to ensure proper fit and finish of Counter-Sink.
- See back of this worksheet for additional construction & options info.

Required Additional Information Choose one from each group and enter price:		Part #		Price
Colors	White	CWH		no charge
	Biscuit	СВІ		no charge
Deck Height	1/2"	CDH1		no charge
	> 1/2" up to 21/8"	CDH2		
	3" up to 6"	CDH3		
Integrated	None	CION		no charge
Overflow	Front bowl installation	CIOF		
	Back bowl installation	CIOB		
Faucet Holes (drilled 1-3/8" in diameter.)	None	CFHN		no charge
	Up to 6	CFH		
Faucet Hole drilling instructions:				

Counter-Sink Options		Part #		Price
Backsplash 4" (H) x 5/8" thick	Length up to 50"	CBSM		
	Length 51" up to 86"	CBLG		
Sidesplash 4" (H) x 5/8" thick	Left	CSL		
	Right	CSR		
Edge Treaments Please specify: Cove (1), Roundover (2), or Roman Ogee (3)		CET_		
Carrier Arms for wall-mounting	Two	CCA2		
	Three	CCA3		
Drain Kit - enter specific part # and price from dealer price sheet				


Edge Treatments - routed edges provide tasteful detail to further integrate with other design elements in the room.


If gloss finish is selected, it will only apply to the sink bowl, top, and vertical surface of the Counter-Sink.

The detail area will remain in a matte finish as denoted by the (*) in the diagrams below.


A 1" minimum counter thickness is required for edge treatments.

Cove Edge part# CET1







Roundover Edge





Roman Ogee Edge part# CET3





Integrated overflow can be installed on either the inside front or back wall of sink. Note: Outside of overflow housing protrudes approx. 1/2" from the bowl and may impact bowl placement.




Backsplash / Sidesplash - measures 4" (H) and 5/8" thick. Field-installed on finished surface of countertop.

Consider bowl placement and/or faucets when ordering.



Overhang is material that extends over the front and/or sides of vanity.

Add a minimum overhang of 1/4" to length & depth, to ensure full coverage of any exposed side of the vanity. Additional overhang may be required depending on installation application or wall variances.



Carrier Arms are offered for wall-mount installation applications. Counter-Sink can be secured to each carrier arm using 3M construction adhesive (not supplied) for most installation applications. Check local codes.

NOTE: carrier arms must be specified on order to ensure proper fit. MTI recommends two carrier arms for most single bowl applications, although three might be necessary for Counter-Sinks 60" and up with an offset bowl.





